






| 課長 | 照査責任者 | 担当 | 作成者 |
|---|--|--|---|
|  |  |   |  |

金田地内水路改修工事

数 量 計 算 書

笛吹市産業観光部農林土木課

金田地内水路改修工事 工事数量総括表

[illegible]

土工数量集計表

| 工種 | 土工 | | | | | |
|----------|------|------|-------|------|---------|----|
| 種別 | 土工 | 作業土工 | | | 作業残土処理工 | 備考 |
| 細別 | 盛土 | 掘削 | 床掘 | 埋戻 | 作業残土処理 | |
| 測点 | | | | 発生土 | | |
| | m3 | m3 | m3 | m3 | m3 | |
| | | | | | | |
| BP～EP | - | - | 12.98 | 7.25 | 4.92 | |
| | | | | | | |
| | | | | | | |
| | | | | | | |
| | | | | | | |
| | | | | | | |
| | | | | | | |
| | | | | | | |
| | | | | | | |
| | | | | | | |
| | | | | | | |
| 補正值 | 1.00 | 1.00 | 1.00 | 1.11 | 1.00 | |
| 合計 (補正後) | - | - | 12.98 | 8.06 | 4.92 | |
| | | | | | | |

作業土工計算書

| 測点 NO | 追加距離 m | 単距離 m | 床掘 | | 埋戻 (発生土) | |
|-----------------|-----------|----------|------|-------|----------|------|
| BP | 0.00 | 0.00 | 0.48 | - | 0.20 | - |
| BP+8.3 (下流) | 8.30 | 8.30 | 0.63 | 4.61 | 0.20 | 1.66 |
| BP+8.3 (上流) | 8.30 | 0.00 | 0.53 | 0.00 | 0.20 | 0.00 |
| No. 1 | 20.00 | 11.70 | 0.23 | 4.45 | 0.20 | 2.34 |
| EP (No. 1+14.5) | 34.50 | 14.50 | 0.25 | 3.48 | 0.20 | 2.90 |
| EP+3.5 | 38.00 | 3.50 | 0.00 | 0.44 | 0.00 | 0.35 |
| | | | | | | |
| | | | | | | |
| | | | | | | |
| | | | | | | |
| | | | | | | |
| | | | | | | |
| | | | | | | |
| | | | | | | |
| | | | | | | |
| | | | | | | |
| | | | | | | |
| | | | | | | |
| | | | | | | |
| | | | | | | |
| | | | | | | |
| 合計 | | 38.00 | | 12.98 | | 7.25 |

構造物撤去工 数量集計表

[illegible]

構造物撤去工計算書

| 測点 NO | 追加距離 m | 単距離 m | 無筋コンクリート m ² | |
|----------------|-----------|----------|----------------------------|------|
| BP | 0.00 | 0.00 | 0.00 | - |
| BP+8.3(下流) | 8.30 | 8.30 | 0.00 | 0.00 |
| BP+8.3(上流) | 8.30 | 0.00 | 0.00 | 0.00 |
| No.1 | 20.00 | 11.70 | 0.00 | 0.00 |
| EP (No.1+14.5) | 34.50 | 14.50 | 0.00 | 0.00 |
| EP+3.5 | 38.00 | 3.50 | 0.20 | 0.35 |
| | | | | |
| | | | | |
| | | | | |
| | | | | |
| | | | | |
| | | | | |
| | | | | |
| | | | | |
| | | | | |
| | | | | |
| | | | | |
| | | | | |
| | | | | |
| | | | | |
| | | | | |
| | | | | |
| | | | | |
| | | | | |
| 合計 | | 38.00 | | 0.35 |

小型水路工 数量集計表

[illegible]

小型水路工調書

測点ピッチ 20.00 m

| 種別 | 細別 | 規格 | 測点 | 中心距離 | 数量 | 備考 |
|-----|------------------|--------------|-------------------------------|------|----------|----|
| 側溝工 | 落ちふた式U型側溝 (PU2型) | 500×500×2000 | BP ~ BP+8.3 (下流) | | 8.30 m | |
| | | 400×500×2000 | BP+8.3 (上流) ~ EP (No. 1+14.5) | | 26.20 m | |
| | | | | | | |
| | 側溝蓋設置 | 400用 | BP+8.3 (上流) ~ EP (No. 5+14.0) | | 8.00 枚 | |
| | | | | | | |
| | | | | | | |
| | 既設管接続 | φ150以下 | | | 10.00 箇所 | |
| | | | | | | |
| | | | | | | |
| | | | | | | |
| | | | | | | |
| | | | | | | |
| | | | | | | |
| | | | | | | |
| | | | | | | |
| | | | | | | |
| | | | | | | |
| | | | | | | |
| | | | | | | |
| | | | | | | |
| | | 合計 | | | 10.00 箇所 | |

間詰工計算書

| 測点 NO | 追加距離 m | 単距離 m | 間詰コンクリート工 18-8-25 | | | |
|-------------------|-----------|----------|----------------------|------|--|--|
| BP | 0.00 | 0.00 | 0.04 | - | | |
| BP+8.3(下流) | 8.30 | 8.30 | 0.04 | 0.33 | | |
| BP+8.3(上流) | 8.30 | 0.00 | 0.04 | 0.00 | | |
| No. 1 | 20.00 | 11.70 | 0.02 | 0.35 | | |
| EP (No. 1 + 14.5) | 34.50 | 14.50 | 0.04 | 0.44 | | |
| EP+3.5 | 38.00 | 3.50 | 0.00 | 0.07 | | |
| | | | | | | |
| | | | | | | |
| | | | | | | |
| | | | | | | |
| | | | | | | |
| | | | | | | |
| | | | | | | |
| | | | | | | |
| | | | | | | |
| | | | | | | |
| | | | | | | |
| | | | | | | |
| | | | | | | |
| | | | | | | |
| | | | | | | |
| | | | | | | |
| | | | | | | |
| | | | | | | |
| | | | | | | |
| 合計 | | 38.00 | | 1.19 | | |

仮設工 数量集計表

[illegible]