

数 量 総 括 表

八千蔵ため池 のり面整形工 数量一覧表

[illegible]

土 工 計 算 書

土工数量計算集計表

		土工			作業土工			作業残土処理工
名 称	延 長	機械掘削	路床盛土		床掘り	埋戻し	基面整正 (L1)	作業残土処理
のり面土工		m3	m3		m3	m3	m2	m3
のり面工	37.20	34.01	3.90					29.68
作業土工								
のり面工	37.20				6.29	3.60	11.16	2.29
水路工	21.80				5.75	2.18	10.90	3.33
合計		34.01	3.90		12.04	5.78	22.06	35.29

のり面工

測 点	距 離	機 械 掘 削		路 床 盛 土			
		断面(m2)	数量(m3)	断面(m2)	数量(m3)		
BP	0.000	0.00	—	0.00	—		
NO.0+1.2	1.200	0.10	0.06	0.00	0.00		
NO.0+5	3.800	0.30	0.76	0.00	0.00		
NO.0+10	5.000	0.30	1.50	0.00	0.00		
NO.0+15.1	5.100	0.40	1.79	0.00	0.00		
NO.0+15.4	0.300	1.90	0.35	0.00	0.00		
NO.1	4.600	1.50	7.82	0.30	0.69		
NO.1+5	5.000	1.70	8.00	0.20	1.25		
NO.1+10	5.000	1.20	7.25	0.20	1.00		
NO.1+16	6.000	0.80	6.00	0.10	0.90		
NO.1+17.2	1.200	0.00	0.48	0.00	0.06		
合計	37.200		34.01		3.90		0.00

のり面工

測点	距離	床掘り		埋戻し		基面整正	
		断面(m2)	数量(m3)	断面(m2)	数量(m3)	幅(m)	数量(m2)
BP	0.000	0.00	-	0.00	-	0.30	-
NO.0+1.2	1.200	0.20	0.12	0.10	0.06	0.30	0.36
NO.0+5	3.800	0.20	0.76	0.10	0.38	0.30	1.14
NO.0+10	5.000	0.20	1.00	0.10	0.50	0.30	1.50
NO.0+15.1	5.100	0.20	1.02	0.10	0.51	0.30	1.53
NO.0+15.4	0.300	0.20	0.06	0.10	0.03	0.30	0.09
NO.1	4.600	0.20	0.92	0.10	0.46	0.30	1.38
NO.1+5	5.000	0.20	1.00	0.10	0.50	0.30	1.50
NO.1+10	5.000	0.10	0.75	0.10	0.50	0.30	1.50
NO.1+16	6.000	0.10	0.60	0.10	0.60	0.30	1.80
NO.1+17.2	1.200	0.00	0.06	0.00	0.06	0.30	0.36
合計	37.200		6.29		3.60		11.16

水路工

測点	距離	床掘り		埋戻し		基面整正	
		断面(m2)	数量(m3)	断面(m2)	数量(m3)	幅(m)	数量(m2)
NO.0+15.4	0.000	0.20	-	0.10	-	0.50	-
NO.1	4.600	0.20	0.92	0.10	0.46	0.50	2.30
NO.1+5	5.000	0.20	1.00	0.10	0.50	0.50	2.50
NO.1+10	5.000	0.30	1.25	0.10	0.50	0.50	2.50
NO.1+16	6.000	0.40	2.10	0.10	0.60	0.50	3.00
NO.1+17.2	1.200	0.40	0.48	0.10	0.12	0.50	0.60
合計	21.800		5.75		2.18		10.90

延長調書

延長調書集計表

[illegible]

構造物延長調書

[illegible]

張りブロック 数量表

製品	規格	仕様	数量	単位	備考
張りブロック 全体m2数量(調整コンクリートを含む)			205.3	m2	標準ブロック(個)×0.8(m2/個)+(端部A+端部B(個))×0.4(m2/個)+調整コンクリート面積(m2)
張りブロック	標準ブロック	標準	208	個	
	端部Aブロック		11	個	
	端部Bブロック		11	個	
アンカーピン	L=300	-	230	本	1(本)/ブロック1(個)
間詰めコンクリート	t=100	-	0.28	m3	標準ブロック(個)×0.0012(m3)
防草シート	-	-	205.3	m2	